



JASPER COUNTY
SOLICITATION #2024-11 RE-BID
ADDENDUM #1
REPLACEMENT FENCING AT SGT. JASPER PARK
March 22, 2024

This Addendum #1 is issued March 22, 2024, to provide the correct scope of work and to answer questions that have been received from potential bidders on the REPLACEMENT FENCING AT SGT. JASPER PARK. All else remains the same.

Scope of Work:

The scope of work has been revised to add additional information regarding posts, line post spacing, use of schedule 40 pipe, the height of the fencing, and the color of the vinyl coating. The entire scope of work is published below.

The contractor will furnish and supply all materials, equipment, and labor required to complete the scope of work as outlined below. This project will consist of, but is not limited to the following:

1. Provide and install 1,452 ft of commercial grade 6 ft high 9-gauge black coated chain link fencing.
2. Provide and install a 6 ft x 28 ft black vinyl coated cantilever roll gate.
3. Provide and install a 6 ft x 20 ft black coated double drive gate.
4. All posts should be set in concrete and set three (3) feet deep.
5. Line post spacing should be ten (10) feet.
6. Pipe shall be Schedule 40.
7. All gate posts should be three (3) feet deep.
8. Grading the ground level for installation of fence.
9. Cleaning of debris on job site daily.
10. Provide necessary permits.